BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37101

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

Name of Work:Earth work and other Works for Temporary tank for lord Ganesh Idols at behind Raghavendra Matta BEL 3rd Block in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of J VIJAY ( )	
				In Figures	In Words
1	28.28	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a	Cum	245.46	Rupees Two Hundred Forty Five and Forty Six Paise Only
2	214.5	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled	Cum	128.15	Rupees One Hundred Twenty Eight and Fifteen Paise Only
3	214.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	160.19	Rupees One Hundred Sixty and Nineteen Paise Only
4	945	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work.	Sqm	4.98	Rupees Four and Ninety Eight Paise Only
5	165	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work.	Each	334.8	Rupees Three Hundred Thirty Four and Eighty Paise Only
6	2.5	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 45 Code 400 metal Component etc complete as per specifications and directions of	Cum	930.0	Rupees Nine Hundred Thirty Only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work.	Hr	39.06	Rupees Thirty Nine and Six Paise Only
8	165	Providing Causal Labours (Unskilled mazdoor Heavy) etc complete as per specifications and directions of engineer in charge of the work.	No	405.67	Rupees Four Hundred Five and Sixty Seven Paise Only
9	800	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing	Mtr	60.45	Rupees Sixty and Forty Five Paise Only
10	3300	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work.	Sft	7.44	Rupees Seven and Forty Four Paise Only
11	1650	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work.	Rft	15.81	Rupees Fifteen and Eighty One Paise Only
12	110	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work.	No	3.72	Rupees Three and Seventy Two Paise Only
13	55	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work.	No	37.2	Rupees Thirty Seven and Twenty Paise Only
14	660	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathed aluminium wire etc complete as per specifications and directions of engineer in charge of the work.	Mtr	8.37	Rupees Eight and Thirty Seven Paise Only
15	55	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work.	Hr	496.62	Rupees Four Hundred Ninety Six and Sixty Two Paise Only
16	66	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work.	No	265.05	Rupees Two Hundred Sixty Five and Five Paise Only
17	6	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work.	Day	3152.7	Rupees Three Thousand One Hundred Fifty Two and Seventy Paise Only

31/08

E.E. (BTP. DIV)

31/08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of J VIJAY ( )	
				In Figures	In Words
18	220	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work.	Cum	198.15	Rupees One Hundred Ninety Eight and Fifteen Paise Only

Signature of the Contractor

Executive Engineer 31/08
Byarayanapura Division
BBMP, Bangalore - 92

31/08